

**Town of Nags Head
Nags Head Cove Water Main Replacement**

Change Order 1

Change Order Proposal Description:

The change order includes installing the watermain at the following location via directional drill in lieu of open cut method:

- Sandpiper Terrace:** STA 34+00 to STA 41+89 790 LF of 8” dia. fusible pipe
- Roanoke Way:** STA 27+90 to STA 22+00 total 590 LF of 6” dia fusible pipe
- Blue Marlin Way** STA 30+30 to STA 25+00 total 530 LF of 6” dia. fusible pipe
- Blue Marlin Way:** STA 17+75 to STA 15+40 total 235 LF of 6” dia. fusible pipe

The change order also addresses the following issue with expanded the drive way cuts.

Driveway Apron expansion from 2.5’ width to 10’ avg. width: Net Area addition: **2,578 Square Yards** *
Total adjusted for 672 SY noted in bid and driveways where HDD is being proposed

Description	Unit	QTY	Unit Price	Extended
8-inch PVC C900, DR18 - Open Cut	LF	-790	\$40.00	(\$31,600.00)
8- inch FPVC C900, DR18 - HDD	LF	790	\$126.00	\$99,540.00
6-inch PVC C900, DR18 - Open Cut	LF	-1355	\$30.00	(\$40,650.00)
6 - inch FPVC C900, DR18 - HDD	LF	1355	\$105.00	\$142,275.00
Concrete Pavement Removal and replacement	SY	2578	\$112.65	\$290,411.70
			Total	459,976.70

Cost of Change Order Increase: \$459,976.70

Nick Brown
Enviro-Tech Unlimited Construction Services, LLC
12/22/2021