

CAPITAL PROJECT IMPROVEMENT UPDATE

The following is intended to provide Town of Nags Head residents with a description, schedule and location of proposed construction projects and the potential conditions that may accompany construction activities. For additional information please contact David Ryan, P.E., Town Engineer at 252.441.6221 or david.ryan@nagsheadnc.gov.



REMEDIAL DRAINAGE IMPROVEMENT PROJECTS

Project Locations

- Memorial Ave.**—western right-of-way margin, spanning from 207 E. Gallery Row to 2434 S. Memorial Ave. **(construction complete)**
- Wrightsville Ave.**—western right-of-way margin, spanning from 2609 S. Croatan Hwy. to 114 E. Baltic St.: eastern right-of-way margin, spanning from 201 E. Admiral St. to 2621 S. Wrightsville Ave. **(construction complete)**
- E. Barnes St.**— northern right-of-way margin, spanning from 2721 S. Croatan Hwy. to 118 E. Barnes St.: southern right-of-way margin, spanning from 107 E. Barnes St. to 2800 S. Wrightsville Ave. **(construction complete)**
- E. Gray Eagle St.**—northern right-of-way margin, spanning from 7127 S. Croatan Hwy. to 7128 S. Virginia Dare Trail: southern right-of-way margin, spanning from 101 E. Gray Eagle St. to 7200 S. Virginia Dare Trail **(construction complete)**
- S. Old Oregon Inlet Rd. (SOOIR)**—western right-of-way margin, proximity of 8810 SOOIR, 8900 SOOIR, 9000 SOOIR, 9100 SOOIR, with replacement of existing cross street drainage pipes. **(construction complete)**
- Mall Dr.** —spanning the width of Mall Dr. adjacent to the Mall Dr. and S. Virginia Dare Trail (NC 12) roadway intersection, with replacement of existing cross street drainage pipes and pavement markings. **(construction complete, pavement marking tentatively scheduled for 4-23-18)**
- Soundside Rd.** —spanning the Soundside Rd. southern right-of-way margin from approximately 329 W. Soundside Rd. to 319 W. Soundside Rd., with replacement of sections of existing storm drainage pipes. **(construction complete)**
- Nags Head Elementary School** —the installation of (2) slotted driveway drain pipes at the north and south driveway school entrances from Wrightsville Ave. **(construction complete)**

Project Descriptions

- Roadway Shoulder Scraping
- Construction of a 1' deep roadway swale with 4:1 horizontal/vertical side slopes
- Post-construction ground stabilization (hydroseeding)
- Storm Drain pipe replacement
- Pavemnt striping

Contractor

RPC Contracting, Inc. Kitty Hawk, NC

Contact Information

RPC Contracting: 252.261.3336, contactus@rpccontracting.com
Town of Nags Head: David Ryan, 252.441.1122, david.ryan@nagsheadnc.gov

What to Expect during construction

- Pedestrian and vehicle access along the road corridor may be restricted during ongoing construction activities.
- It is possible that customers will be without water for a short duration (typically a few hours) while this work is in progress. Property owners will be notified in advance regarding any planned service disruptions.
- Town services will continue uninterrupted.

